



Harvey Construction Corporation  
10 Harvey Road  
Bedford, NH 03110  
Telephone (603) 624-4600  
Facsimile (603) 668-0389  
www.harveyconstruction.com

February 3, 2015

**Capt. William Breault**  
**Dover Police Department**  
**Field Operations Division**  
**Dover, NH Police Department**

RE: Recommendation of Award  
**Metro Walls, Inc.**  
**FRAMING & DRYWALL**  
Dover Police Facility and Public Parking Garage/Orchard Street Reconstruction

Dear Mr. Breault,

Harvey Construction is seeking approval to award the **FRAMING & DRYWALL** contract for subject project to **Metro Walls, Inc.** for the total amount of **Five Hundred Forty Three Thousand Two Hundred Five Dollars and 0.00/100 (\$543,205)**. Scope of work in accordance with the Dover Police Facility and Public Parking Garage Plans dated 11/17/14, Site Development Plans dated 6/30/14 and Orchard Street Reconstruction – Subdivision Plans dated June 2014 prepared by CLD Engineers and Lavallee Brensinger.

If you have any question or concerns, please advise.

Very Truly Yours,

Harvey Construction Corporation

Andrew P. Martino, P.E., LEED AP  
Project Manager

I hereby authorize Harvey Construction to enter into a contract agreement with the aforementioned subcontractor/supplier on behalf of the City of Dover for the amount stated above.

  
**Capt. William Breault**

2/3/15  
Date

Harvey Construction		Bid Tabulation Sheet					
Job: DOVER PD/PARKING GARAGE		Bid Date: 12/19/2014					
Trade:	DRYWALL	HCC Budget	Co. Metro Walls	Co. Chris's Drywall	Co. VPS	Co. Rolands	
Spec. Sections:	Division #9 05 40 00, 09 21 16		Contact: John Boule	Contact: Steve Blanchette	Contact: Dennis	Contact: Shawn Aube	
			Phone: 668-2648	Phone: 731-3919	Phone: 889-6035	Phone: 207-375-4410	
			12/19/2014	12/19/2014			
Scope Check List	POLICE STATION	\$ 524,515	\$ 543,205	\$ 543,715	NO BID RECEIVED	NO BID RECEIVED	
Base Bid	PARKING GARAGE	\$ -	\$ -	\$ -			
Documents	Dover Police Facility and Public Parking Garage Vol #1, dated November 17, 2014. Dover Police Facility and Public Parking Garage Vol #2, dated November 17, 2014. Dover Police Facility and Public Parking Garage – Site Development Plans 6/30/14 Orchard Street Reconstruction – Subdivision Plans June 2014 Dover Police Facility and Public Parking Garage – Site Landscape Plan 6/25/14 Specifications: Dover Police Facility and Public Parking Garage, Dover New Hampshire, dated November 17, 2014.						
RFI's	1 to 11						
Addendum	RFI #12 - Issued 12/18/14 Post Bid Review 1 & 2						
SCHEDULE	Per HCC Project Schedule dated 12/10/14						
Scope	<ul style="list-style-type: none"> <li>Exterior Mock-Up</li> <li>Engineered Shop Drawings</li> <li>G-60 Coated LGMF Exterior</li> <li>G-40 Coated LGMF Interior</li> <li>Durock at Restroom Wet Walls &amp; Shower Stalls</li> <li>Abuse Resistant GWB at Intake &amp; Holding Rooms /Ceilings</li> <li>Bullet Resistant Fiberglass Panels</li> <li>Shaft Walls</li> <li>9ga Metal Mesh at Security Ceilings</li> <li>16ga Metal Mesh at Security Walls</li> <li>Level 5 Finish Over Abuse Resistant Walls at Intake &amp; Holding Rooms</li> <li>Fiberglass Insulation at Interior Partitions</li> <li>Inwall Blocking</li> <li>2x FireTreated Wood Blocking at Exterior Windows &amp; Door Ros</li> <li>FireTreated Plywood at Security Walls</li> <li>2 layers of PT Blocking at LGMF - Roof Parapet A3.10</li> <li>Acoustic Smoke Seal, Fire spray w/ Insulation at Rated Partitions - per Partition Schedule</li> <li>Unloading/Distribution of HM Doors &amp; Frames</li> <li>Furring Around SS Crossbraces at Stair A - per I12/A4.21</li> </ul>						
Total		\$ 524,515	\$ 543,205	\$ 543,715	\$ -	\$ -	
Value Engineering	1 Delete Furring Around SS Crossbraces at Stair A - per I12/A4.21						
			\$ (4,335)				



COMMERCIAL FRAMING & DRYWALL SPECIALISTS

**Harvey Construction Corporation**

10 Harvey Road  
Bedford, NH 03110  
603-624-4600 (t)  
603-668-0389 (f)

**Attention:** Joe Pollock

**Date:** December 19, 2014  
**Job Name:** Dover Police Facility  
**Location:** Dover, NH  
**Architect:** Lavalley / Brensinger  
**Plans Dated:** 11/17/14 (Construction Documents)

**REVISED PROPOSAL**

**Furnish labor and materials as follows:**

1. Addendum #1, Addendum #2, RFI's 1 thru 11
2. Provide open shop labor
3. Provide exterior Mock-up
4. Provide engineered stamped exterior LGMF shop drawings G-60 material coating
5. Provide engineered stamped interior LGMF shop drawings G-40 material coating
1. Provide LGMF at exterior walls, parapets, canopies and canopy ceilings
6. Provide Standard 2" deflection track at interior / exterior walls
7. Provide 20ga (33mil) metal stud and track at interior walls and soffits
8. Provide metal suspended ceiling framing for installation of GWB
9. Provide 5/8" GWB on all walls, ceilings and soffits
10. Provide Mold Tough GWB at restroom that do not receive wall tile
11. Provide 5/8" Durock at restroom wet walls and shower stalls only
12. Provide 5/8" Dens-glass exterior sheathing
13. Provide 5/8" abuse GWB at intake and holding room ceilings A1.5
14. Provide 7/16" level 3 FG300 Fiberguard Fiberglass wall Armor panels
15. Provide 1" shaft liner with 6" J-Track and C-H studs at shaft walls
16. Provide 16ga flatted expanded metal mesh at security wall S49 and S51
17. Provide 9ga flatted expanded metal mesh at intake and holding room ceilings A1.5
18. Provide level 4 finish ready for paint at all walls, ceilings and soffits
19. Provide level 5 finish ready for paint at intake and holding room ceilings over abuse GWB
20. Provide either R11 or R19 unfaced batt insulation at interior walls and roof parapets only A3.10
21. Provide 2x6 in-wall blocking attached to metal stud framing only
22. Provide 2x FT wood blocking at exterior window and door rough openings A3.11
23. Provide 3/4" FT plywood at security wall S49 and S51
24. Provide (2) rows of 2x10 PT wood blocking at LGMF roof parapet A3.10
25. Provide 3/4" FT plywood at break room locker base
26. Provide metal corner bead and plastic tear-away trim at exterior window / door openings
27. Provide acoustical smoke sealant or fire spray with firesafing at top of smoke / rated walls
28. Provide unloading, distribution and installation of HM welded door frames in metal framing only
29. Provide daily clean-up of our debris to an on-site dumpster (Dumpster provided by others)
30. Provide loading of material thru an open window on each floor
31. Normal business hours
32. Provide interior / exterior lifts for our work
33. Provide supervision for our work

**SEE NEXT PAGE FOR ADDITIONAL INFORMATION.....**



COMMERCIAL FRAMING & DRYWALL SPECIALISTS

Base Bid.....\$543,205.00

**Exclusions:**

2. All exterior air/moister barrier
3. Temporary lighting, heat, ventilation and protection
4. Temp safety rails, Temp walls
5. Off hours
6. Police details
7. Fire caulk, fire pillows and firesafing at rated thru wall penetrations by others
8. All doors and hardware
9. ACT
10. Level 5 finishes
11. Fire stop tracks
12. Welding of LGMF or 9ga or 16ga expanded metal mesh
13. Spray applied texture finishes
14. Access panels
15. Putty packs at electrical outlets
16. Interior / exterior finish carpentry
17. Wall protection and corner guards
18. Installation of 7ga chase panel F6/A8.1
19. PL on 5/8" surface mounted plywood and stainless steel shape G5/A7.1
20. All work at parking garage
21. Installation of aluminum window and door frames
22. Exterior wall insulation A3.10

**NOTE:**

This proposal may be rescinded if not accepted within thirty days and is subject to approval of the construction schedule. Please feel free to give me a call if you have any questions.

John Boule'  
Estimator / Project manager